Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work: Providing Children Play Equipments and Senior Citizen Gym Equipments and Landscape Development to Parks in Ward no. 07, Kodigehalli of Yelahanka Zone

DETAILED QUANTITY CALCULATION & COST ESTIMATE

Behind Gundanjaneya Temple

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
A	**Civil Works**								
1	KSRBB M200-10.1. **Clearing and grubbing road land** including uprooting rank vegetation, grass, bushes, stumps, saplings and trees girth up to 300mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness complete as per specifications. I. By Manual Means: A. In area of light jungle. MORTH Specification No. 201. (BCSR 2016-2017, Page 136, Item No 18.13)								
	Basic Rate	48878.00							
	Add Area weightage of 8%	3910.24							
	Sub Total	52788.24		As per drawing					
	Total Area	**Ha**	1	5771.00			5771.00		
							0.58	**52788.24**	**30465.00**
2	**Excavation in Soil with Dozer** KSRBB M300-11. Excavation for road way in all types of soil by mechanical means including cutting and pushing the earth to site of embankment including trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections complete as per specifications. MORTH Specification No. 301. (BCSR 2016-2017, Page 143, Item No 19.11)								
	Basic Rate	68.00							
	Add Area weightage of 8%	5.44							
	Sub Total	73.44							
	Lead 15 Kms	116.00							
	Total	189.44							
	Lowering & Levelling	**Cum**		As per drawing		Avg			
	Total Area		1	5771.00		0.25	1442.75		
	For Walking Track - alround								
	Walking Track		1	275.00	2.50	0.10	69.00		
	For Chain Link Fencing - alround								
	Chain Link Fencing		1	353.00	0.75	0.75	199.00		
							1710.75	**189.44**	**324085.00**
3	KSRB 2.2.6 : Excavation 1.5m and above in width in hard rock by chiselling and / or wedging, where blasting is prohibited for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m. in depth stacking the excavated stuff clear from the edge of excavation with lead upto 50m including cost of labour complete as per specifications. Specification. No. KBS (BCSR 2016-2017, Page 5, Item No 2.8)								
	Basic Rate	1266.00							
	Add Area weightage of 8%	101.28							
	Total	1367.28							
		Cum							
	For Walking Track - alround								
	Walking Track		1	10.00	7.80	0.60	47.00		
							47.00	**1367.28**	**64263.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
4	**KSRRB M300-Construction of Embankment with Material Gravel/Murrum** KSRRB M300-53. Construction of embankment with approved material Gravel /Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (BCSR 2016-2017, Page 148, Item No 19.60)								
	Basic Rate	302.00							
	Add Area weightage of 8%	24.16							
	Sub Total	326.16							
	Lowering & Levelling								
	vide item no. 2								
	Play Area	**Cum**	1	5771.00		0.25	1442.75		
	Open Gym Platform		1	20.00	15.00	0.45	135.00		
							1577.75	**326.16**	**514599.00**
5	KSRRB M400- Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P.No.158 I.No.20.18)								
	Basic Rate	1668.00							
	Add Area weightage of 8%	133.44							
	Sub Total	1801.44							
	For Walking Track - alround								
		Cum	1	275.00	2.50	0.20	306.00		
							306.00	**1801.44**	**551241.00**
6	KSRB 4-1.3 : Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 (BCSR 2016-2017, Page 12, Item No 4.3)								
	Basic Rate	4867.00							
	Add Area weightage of 8%	389.36							
	Sub Total	5256.36							
	For Walking Track - base								
	Walking Track	**Cum**	2	275.00	0.18	0.15	14.85		
	Open Gym Platform		1	20.00	15.00	0.15	45.00		
	Open gym platform		2	36.00	0.18	0.15	1.94		
	For Chain Link Fencing								
	Chain Link Fencing		1	353.00	0.75	0.15	39.71		
	Benches surround		15	1.50	2.10	0.10	4.73		
							106.23	**5256.36**	**558392.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
7	KSRB 14.6-1: Providing and laying **heavy duty cobble stones 60mm thick** interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS. (BCSR 2016-2017, Page 101, Item No 14.6)								
	Basic Rate	912.00							
	Add Area weightage of 8%	72.96							
	Sub Total	984.96							
	For Walking Track - base								
	Walking Track	**Cum**	1	275.00	2.30		632.50		
							632.50	**984.96**	**622988.00**
8	KSRB 5.2-2 : Providing and constructing **granite / trap / basalt size stone masonry** in foundation with cement mortar 1 : 6 stone hammerd dressed in courses not less than 20 ems high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (BCSR 2016-2017, Page 23, Item No 5.5)								
	Basic Rate	4187.00							
	Add Area weightage of 8%	334.96							
	Sub Total	4521.96							
	For Chain Link Fencing	**Cum**	1	65.00	0.75	0.75	36.56		
			1	353.00	0.60	0.45	95.31		
			1	353.00	0.45	0.45	71.48		
			-177	0.45	0.45	0.45	-16.13		
							187.23	**4521.96**	**846628.00**
9	KSRB 4-1 .6 ; Providing and laying in position **plain cement concrete of mix 1:2:4** with cement@ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.(BCSR 2016-2017, Page 12, Item No 4.6)								
	Basic Rate	5441.00							
	Add Area weightage of 8%	435.28							
	Sub Total	5876.28							
	Coping								
	Chain Link Fencing	**Cum**	177	0.45	0.45	0.45	16.13		
			1	353.00	0.45	0.10	15.89		
	Open gym equipment fixing		30	0.60	0.60	0.45	4.86		
							36.87	**5876.28**	**216683.00**
10	Providing and laying/fixing cement base, precast, pre polished cement concrete, **designer tiles 25mm thick for flooring** conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification (BCSR 2016-2017, Page 109, Item No 14.62)								
	Basic Rate	1085.00							
	Add Area weightage of 8%	86.80							
	Sub Total	1171.80							
	Open gym	**Sqm**	1	20.00	15.00		300.00		
	Benches surround		15	1.50	2.10		47.25		
							347.25	**1171.80**	**406908.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
11	KSRRB M2200-8.1. **Back filling** behind abutment, wing wall and return wall complete as per drawing and Technical Specification complete as per specifications. A. Granular material MORTH Specification No. 2204 (BCSR 2016-2017, Page 225, Item No 28.11)								
	Basic Rate	524.00							
	Add Area weightage of 8%	41.92							
	Sub Total	565.92							
	Chain Link Fencing	**Cum**	1	353.00	0.20	0.60	42.36		
							42.36	**565.92**	**23973.00**
12	Providing **chain link fencing** 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (BCSR 2016-2017, Page 262, Item No 37.3)								
	Basic Rate	659.00							
	Add Area weightage of 8%	52.72							
	Sub Total	711.72							
	Chain Link Fencing	**Sqm**	1	353.00		2.10	741.30		
							741.30	**711.72**	**527599.00**
13	Supplying and fixing **M.S. Rectangular poles** made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1 :2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 ems. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (BCSR 2016-2017, Page 262, Item No 37.2)								
	Basic Rate	819.00							
	Add Area weightage of 8%	65.52							
	Sub Total	884.52							
	Chain Link Fencing	**m**	177	2.55			451.35		
							451.35	**884.52**	**399229.00**
14	Providing and fixing **M.S. Block pipe** of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint (BCSR 2016-2017, Page 262, Item No 37.4)								
	Basic Rate	324.00							
	Add Area weightage of 8%	25.92							
	Sub Total	349.92							
	Chain Link Fencing	**m**	3	353.00			1059.00		
							1059.00	**349.92**	**370566.00**
15	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of the Engineer-in-charge of the work. (Data Rate)								
	Data Rate	12475.03							
	Gate	**Sqm**	1	3.00	3.20		9.60		
							9.60	**12475.03**	**119761.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
16	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (BCSR 2016-2017, Page 25, Item No 5.26.1)								
	Basic Rate	937.00							
	Add Area weightage of 8%	74.96							
	Sub Total	1011.96							
	Steps	**Sqm**	3	6.00	0.20		3.60		
							3.60	**1011.96**	**3644.00**
17	KSRB15-3.7 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (BCSR 2016-2017, Page 113, Item No 15.15)								
	Basic Rate	244.00							
	Add Area weightage of 8%	19.52							
	Sub Total	263.52							
		Sqm	2	6.00	0.30		3.60		
			2	6.00	0.30		3.60		
							7.20	**263.52**	**1898.00**
18	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete (BCSR 2016-2017, Page 182, Item No 24.1)								
	Basic Rate	313.00							
	Add Area weightage of 8%	25.04							
	Sub Total	338.04							
	For Walking Track	**Nos**	2	275.00			550.00		
	Open gym platform		2	36.00			72.00		
	A					**A**	**622.00**		
	B=A/.045					**B**	**1382.00**	**338.04**	**467172.00**
19	KSRRB 800-1. **Painting two coats** after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8. (BCSR 2016-2017, Page 182, Item No 24.1)								
	Basic Rate	60.00							
	Add Area weightage of 8%	4.80							
	Sub Total	64.80							
	For Walking Track	**Sqm**	2	275.00	0.35		192.50		
	Open gym platform		4	20.00	0.35		28.00		
	Steps		4	6.00	0.30		7.20		
							227.70	**64.80**	**14755.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
20	Supply and Fixing of Pull Down Challenger. Metal: All tubular steel of 2 .5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All weld d joints are scalloped as necessary and welded to an approved MIG process.All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at II the welding points prior to finishing . All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. Allmetal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for th e handles. Bearings:Maintenance-free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified internat ional certifying agency such as IPEMA,TUV,CPSC, or SGS only.The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS ma rk as has been issued in the EN16630 safety certificates. Size_ L x W x H): 2570 x 805 x 2685 mm. Weight: 85.4 Kg Safety Area : 6287 x 4858 mm Capacity_2 Persons.								
	Data Rate	240000.00							
		Unit	1				1.00		
							1.00	**240000.00**	**240000.00**
21	Supply and fixing of Seated Chest Press. Metal: All tubular steel of 2.Smm thikness are galvanized and z inc dipped. Joints are Robotic welded. All welded joints t1H • scalloped as necessary and welded to an approved MIG process. All welds an• 111 csed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w 11lt1ing points prior to finishing. All metal parts are powder coated using AKZO Nobel (11 ca t Wall powder to the thickness of 80-120 microns. All metal parts are tested in rn 1r a lt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handle!,,Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely Prt' ,ssembled equipment modules. Maintenance: Maintain according to EN 166630 and the maintenance guide. Safety: All products must be tested and certified to mt•(•lEN16630 safety standards with GS test mark. The EN 16630,certificates must be issued by a reputed notified international certifying agency such as IPEMA, 1UV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS inark as has been issued in the EN16630 safety certificates. All products must carry n GS mark :in it.. Size_ L x W x H): 1955 x 733 x 2058 mm. Weight : 86.6 Kg Safety Arc:.1: 5545 x 4470 mm Capacity_2 Persons.								
	Data Rate	230000.00							
		Unit	1				1.00		
							1.00	**230000.00**	**230000.00**
22	Supply and fixing of Self Weighted Rower. Metal: All tubular steel of 2.Smm thit.kness are galvaniied and zinc dipped. Joints are Robotic welded. All welded joiflts arc • scalloped as necessary and welded to an approved MIG process. All welds arc dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our sa lt S'PI,ray machine.that uses a 5% NaCl solution in accordance to IS07227 to speed up3 c_6rrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintain according to EN 16630 and the maintenance guide. Safety:All products must be tested and certified to meet EN16630 safety standards only by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS. The GS Mork• EN16630 Certificates must be in the name of tendering party and not any 3rd p;:11 ty All products must carry a GS mark on it.. Size_L x W x H}: 1390 x 805 x 1100 mm. Weight: 42.4 Kg Safety Area: 3790 x 3205 mm Capacity_1 Person.								
	Data Rate	165000.00							
		Unit	1				1.00		
							1.00	**165000.00**	**165000.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
23	Supply and fixing of Elliptical Cross Trainer. Metal: All t\jbular steel of 2.Smm thickness are galvanized and zinc dipped. Joints are RClbotic welded. All weldecl 1oints a re scalloped as necessary and welded to an approve(j MIG process. All welds .i re dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at .ill the welding points prior to finishing. Alt metal parts are PCl\vder coated using AKZO Nobel Great Wall powder to the thickness of 80-120 microns. All metal parts are testecJ in our salt spray machine that uses a 5% NaCl solution iri ilccordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely.pre-assembled equipment modules. Maintenance: Maintain according to EN 1G630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards w ith GS test mark.The EN 16630 certificates must be issued by a reputed notified international certifying agl!ncy uch as IPEMA,TUV ,CPSC, or SGS only .The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with 1 he tender document. Alt products must clearly display tt) GS mark as has been i ued in the EN16630 safety certificates. Size_L x W x H):126/ 582 x 1764 mm. Weight : 43.5 Kg Safety A rea: 4322 x 3632 mm Capacity 1Person.								
	Data Rate	140000.00							
		Unit	1				1.00		
							1.00	**140000.00**	**140000.00**
24	Supply and Fixing of Rider. Metal: All tubular steel of 2.smm thickness are galvd 1 ilzed and zinc dipped . Joints are Robotic welded. All weldect joints are scalloped as necessary and welded to an approved MIG proi;ess. .<\11 welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing.All metal parts are powder Clated using AKZO Nobel-G reat Wall powder to the thickness of 80-120 microns. All ll\etal parts are tested in our sa lt spray machine that uses a 5% NaCl solution in accorcJ<ince to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubher is used for the handles. 5 Bearings : Maintenance-free ball bearings...Scope of c:l livery: 1completely pre-assembled equipment modules. Maintenance: Maint<1in according to EN 16630 a nd the maintenance guide. Safety: Alf products must b tested and certified to meet EN16630 safety standards with GS test mark. The El\! 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV ,CPSC, or SGS only. The GS Mark-EN16630 Certificate must be in the name of tendering party and not any 3rd party. All products 'hust clearly display the GS mark as has been issued in the EN 16630 safety certificat . Size L x w x H): 910 x 655 x 1270 mm. Weight : 29.5 Kg Safety Area: 3310 x tnm C;pacity_l Person								
	Data Rate	90000.00							
		Unit	1				1.00		
							1.00	**90000.00**	**90000.00**
25	Supply and Fixing of Bicycle. Metal: All tubular steel of 25mm thickness are galvani zed and zinc dipped. Joints are Robotic welded. All welded joint s are S('.llloped as necessary and w eldea to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the weltling points prior to finishing.All metal parts are powder coated using AKZO Nobel GreatWall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt v pray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up -orrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. each 1 125000 125000 131188 131188 134500 134500 Bearings: Maintenance-free ball bearings . Scope of delivery: 1completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to mee t EN16630 safety standards only by a reputed notified international certifying acency such as IPEMA,TUV,CPSC, or SGS. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. Size_L x W x H): 1000 x 498 x 120 mm. Weight : 51.5 Kg Safety Area: 3400 x 3498 mm Capacity_ 1 Persons.								
	Data Rate	125000.00							
		Unit	1				1.00		
							1.00	**125000.00**	**125000.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
26	Supply and Fixing of Arm & Pedal Bike. Metal: All tubular steel of 2.Smm thickness a re galvanized and zinc dipped.Joints are Robotic welded.All welded joints are sca lloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles.Bearings : Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide.Safety : All products must be tested anEI certified to meet EN16630 safety standards only by a reputed notified international certifying agencv such as IPEMA,TUV, CPSC, or SGS. The GS Mark- EN16630 Certificates must be in t he name of tendering party and not any 3rd party.Size_L x W x H}: 830 x 500 x 1450 mm. Weight: 32 Kg Safety Area: 3830 x 2900 mm Capacity_ 1Persons.								
	Data Rate	170000.00							
		Unit	1				1.00		
							1.00	**170000.00**	**170000.00**
27	Supply and Fixing of Tai Chi Spinners . Metal: All tubular steel of 2.Smm thicknp<.s are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sc;illoped as necessa ry and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w eldin points prior to finishing. All metal parts are powder coated using AKZO Nobel G reat Wall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to JS07227 to speeu up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance -free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintena nce:Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUY, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. Thecertificates must be attached with the tender document . All products must clearly -display the GS mark as has been issued in the EN15630 safety certificates. Size_ L x W x H): 1120 x 1150 x 1620 mm. Weight: 39 Kg Safety Area: 3520 x 3550 mm Capacity_3 Persons.								
	Data Rate	115000.00							
		Unit	1				1.00		
							1.00	**115000.00**	**115000.00**
28	Supply and fixing of Twist Stepper. Metal: All tubular steel of 2.Smrn thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sca lloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-GreatWall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark.The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV ,CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates . Size_ L x W x H): 1395 x 650 x1750 mm. Weight: 53.8 Kg Safety Area.: 3795 x 3050 mm Capacity_2 Persons.								
	Data Rate	180000.00							
		Unit	1				1.00		
							1.00	**180000.00**	**180000.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
29	Supply and fixing of Big Shoulder Wheel. Metal: All tubular steel of 2.Smni l111ckness are galvanized and zinc dipped. Joints are Robotic welded. All welded joint ure scalloped as necessary and welded to an approved MIG process. All welds arc' dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w elding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles.CV-10 Bearings: Maintenance-free ball bearings. Scope of delivery:1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to rneet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size_L x W x H): 845 x 810 x 1710 mm. Weight: 34 Kg Safety Area: 3224 x 3376 mm Capacity_2 Persons.								
	Data Rate	120000.00							
		Unit	1				1.00		
							1.00	**120000.00**	**120000.00**
30	Supply and fixing of HD Health Walker. Metal: All tubular steel of 2.Smm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joint s arescalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a S% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bea rings.11 Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EQ_and the maintenance guide.Safety: All productsmust be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS oniy. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with the tender document . All products must clearly display the GS mark as has been issued in the EN16630 safety certificates .Sizelx W xH): 1065 x 61S x 1364 mm.Weight: 51Kg. Safety Area: 4090 • 3555mm. Capacity 1 Person								
	Data Rate	140000.00							
		Unit	1				1.00		
							1.00	**140000.00**	**140000.00**
31	Supply and fixing of HD Squat Pushing. Metal:All tub.ular steel of 2.Smm1hicknos are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sca lloped as necessary: and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing . All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our sa lt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles 13 Bearings: Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules.Maintenance: Maintain according to EN 16630 andthe maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only .The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS ma rk as has been issued in the EN16630 safety certificates.Sizelx W x H): 2270 x 635 x 1640 mm. Weight: 60.2Kg.Safety Area: 5300 * 3685mm. Capacity 2 Persons								
	Data Rate	215000.00							
		Unit	1				1.00		
							1.00	**215000.00**	**215000.00**

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
332	Supply and fixing of HD Waist Twister. Metal : All tubular steel of 2.Smm thic k11ess are ga:vanized and zinc dipped. Joints are Robotic welded. All welded joints are scJlloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns.Al l metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up rrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. arings : Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance : Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA,TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size_L x W x H}:1460 x 1310 x USO mm. Weight: 39.1 Kg Safety Area : 4360 x 4510 mm Capacity_3 Persons.								
	Data Rate	130000.00							
		Unit	1				1.00		
							1.00	**130000.00**	**130000.00**
333	Supply and Fixing of HD.Mini Ski. Metal:All tubular steel of 2 .Smm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed offremoving all sha rp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing.All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintenan(;:e :Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meetEN16630 safety standards with GS test mark.The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV,CPSC, or SGS only.The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS mark as has been issued in the EN16630 safety certificates.Size_L x W x H): 1214 x 900 x1347 mm. Weight: 45 Kg Safety Area : 4214 x 3900 mm Capacity_2 Persons.								
	Data Rate	160000.00							
		Unit	1				1.00		
							1.00	**160000.00**	**160000.00**
334	Supply and fixing of HD Double Health Walker. Metal: All tubular steel of 2.50mm thickness are galvanized and zinc dipped. Joints are Robotic welded . All welded joints are scalloped as necessary and welded to an approved MIG process. All welds a re dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied ut all the welding points prior to finishing. All metal parts are powder coated using AK ZO Nobel Great Wall powder to the thickness of 80-120 microns. All metal parts are test ed in our salt spray machine that uses a 5% NaCl solution in accordance to 1507227 to peed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the tlandles. Bearings: Maintenance-free ball bearings.Scope of delivery : 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must besuch as IPEMA, TUV,issued by a reputed notified international certifying agency CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS mark as has been issued in the EN16630 safety certificates.Sizel x W x H): 2015 x 615 x 1360mm .Weight: 93Kg. Safety Area: 5015 • 3015mm. Capacity2 Person								
	Data Rate	240000.00							
		Unit	1				1.00		
							1.00	**240000.00**	**240000.00**
335	Providing and fixing granite benches as per design, specification and fixing as per the directions of the engineer in charge.								
	Data Rate	10550.00							
		Unit	15				15.00		
							15.00	**10550.00**	**158250.00**